



हिन्दुस्तान

www.livehindostan.com

अपना पश्चिम चंपारण

नृत्या

818888

DT. 08/02/26

H.S. DAV PUBLIC SCHOOL

NARKATIAGANJ, WEST CHAMPARAN, BIHAR-845455, E-mail: hsdavnke@gmail.com

TENDER NOTICE

Sealed quotations are invited from reputed firms for demolition and reconstruction of the collapsed boundary wall of the school playground.

The quotations are also invited for school buses on hire basis (Valid Registration) apply by 14.02.2026.

For details, contact: 9399928465/

www.hsdavnarkatiaganj.org/ hsdavnke@gmail.com

M. K. Tiwari
Principal

B. K. Sahu
Manager

Shanti Singh
ARQ, BR Zone-B

ABSTRACT OF COST OF CONSTRUCTION OF COMPOUND WALL IN COLLAPSED PORTION OF

HYDERABAD SATYAGRAH D.A.V. PUBLIC SCHOOL, NARKATIAGANJ, WEST CHAMPARAN, BIHAR.

Sl.No.	S.O.R.	DESCRIPTION	QTY.	UNIT.
		(A) Addition of Compound wall in collapsed portion- Length=182'6"+17'+49'-6"=249'		
		Area of construction of addition of Compound wall=2945.67 SFT (273.76 SM)		
		SECTION-I (EARTHWORK/SAND FILLING)		
1	2.8	Earth work in excavation in foundation trenches or drains (not exceeding 1.5m in width or 10sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5m including getting out the excavated soil and disposal of surplus excavated soil as directed with in a lead of 50m.		
	2.8.1	All kinds of soil.	88.46	Cum
		SECTION-II (P.C.C./R.C.C. WORK)		
2	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work upto plinth level.		
	4.1.5	1:3:6 (1 cement, 3 coarse sand, 6 graded stone aggregate 20mm nominal size.)	5.53	Cum
3	5.1	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement - All work upto plinth level		
	5.1.2	1:1.5:3 (1 cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size)	39.75	Cum
4	5.2	Reinforced cement concrete work in wall (any thickness) including attach pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and strut etc. upto floor five level excluding cost of centering, shuttering finishing and reinforcement.		
	5.2.2	1:1.5:3 (1 cement; 1.5 coarse sand; 3 graded stone aggregate 20mm nominal size.)	7.53	Cum
5	5.3	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15, landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to floor five level excluding the cost of centring, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement: 1.5 coarse sand: 3 graded stone aggregate		

Sl.No.	S.O.R.	DESCRIPTION	Qty.	Unit.
		20mm nominal size).	11.42	Cum
6	5.9	Centering and shuttering including strutting propping etc and removal of form for		
	5.9.1	Foundations, footings, bases of column etc. for mass concrete.	54.48	Sqm
	5.9.5	Lintels, Beams, plinth beams, girders, bressumers and cantilevers.	211.38	Sqm
	5.9.6	Columns, pillars, piers, abutments posts and struts.	256.73	Sqm
7	5.22	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete.		
	5.22.1B	Mild steel-6mm dia.	60	Kg
	5.22.7A	Thermo-Mechanically treated bars TMTC-500-8mm dia.	1526	Kg
	5.22.7B	Thermo-Mechanically treated bars TMTC-500-10mm dia.	889	Kg
	5.22.7C	Thermo-Mechanically treated bars TMTC-500-12mm dia.	3800	Kg
		SECTION-III (BRICKWORK)		
8	6.1A+ 6.1.14A+ 6.3A	Brickwork with bricks of class designation 100A in superstructure above plinth level up to floor level in Cement mortar 1:6 (1 cement; 6 coarse sand)	50.25	Cum
9	6.18A+	Half brick masonry with bricks of class designation 100A in foundations and plinth		
	6.18.4A	Cement mortar 1:4 (1 cement; 4 coarse sand)	5.78	Sqm
	6.19A	Extra for half brick masonry in super structure above plinth level up to floor level.	5.78	Sqm
		SECTION-IV (FLOORING WORK)		
10	11.72	Providing designation 100A one brick flat soling joints filled with local sand including cost of watering, taxes, royalty all complete as per building specification and direction of E/I.	110.95	Sqm
		SECTION-V (PLASTER WORK)		
11	13.11	12mm cement plaster of mix:		
	13.11.4	1:6 (1 cement; 6 coarse sand).	420.07	Sqm
12	13.12.	15mm cement plaster on rough side of single or half brick wall of mix.		
	13.12.4	1:6 (1 cement; 6 coarse sand).	289.27	Sqm
		SECTION-VI (FINISHING WORK)		
13	13.46A	Finishing walls with premium Acrylic Smooth exterior paint with silicone additives of required shade:		
	13.46A.1	New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	709.34	Sqm
		TOTAL		

Sl.No.	S.O.R.	DESCRIPTION	Qty.	Unit.	Rate
		ROUNDUP			
		Costofconstructionpersq.ft.			

FOR TECHNICAL APPROVAL

**ABSTRACT OF COST OF CONSTRUCTION OF COMPOUND WALL IN COLLAPSED PORTION OF
HYDERABAD SATYAGRAH D.A.V. PUBLIC SCHOOL, NARKATIAGANJ, WEST CHAMPARAN, BIHAR.**

Sl. No.	S.O.R.	DESCRIPTION	QTY.	UNIT.	
		(B) Demolishing collapsed compound wall - Length = $182'6'' + 17' + 49' - 6'' = 249' - 0''$, Ht. = 11'			
		Area of demolished Compound wall = 2945.67 SFT (273.76 SM)			
		SECTION-I (DEMOLITION WORK)			
1	15.7	Demolishing brick work including stacking of service-able material and disposal of unserviceable material within 50 meters lead:			
	15.7.4	Incement mortar	50.25	Cum	
2	15.3	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metres lead.			
			31.30	Cum	1
		TOTAL			
		ROUNDUP			
		Cost of demolition per sq.ft.			